



Modern Hydraulic LLC

1750 ton SOUTHWARK [Stock Number 136]

Construction	4 Posts, 11-1/2" Dia. Each
Stroke	48"
Daylight Opening	72" daylight can be extended
Bed & Slide Working Area	12' L-R x 11' F-B or 8' L-R x 16' F-B
Distance Between Posts	12' L-R x 8' F-B
Bed & Slide Overall	16' L-R x 11' F-B, "T" Slotted
Slide	Fully Guided
Main Rams	(3) 26" Dia. Each @ 2200 PSI

Press Can Be Run In Increments of 580 Tons: 1, 2 or 3 Rams

Push Ups (4): 7" Dia. Each, Total Lifting Tonnage 115 @ 1500 PSI.
All mounted in 4 corners of the bed.

Knockouts
(3), 40 tons each
(1) center of bed, 36" stroke
(2) end of bed, adjustable 24" on long axis of bed, 24" stroke each

Mounted on Press Crown Prefill Tank, (1) 5" Prefill Valve

Manually Operated Lever Control Valves Replaced w/Electrical Controls 1965.

All Operator Controls Mounted in a Pendant with the following: Selector switch for tonnage Changes, Rapid Advance "Down" for any Press Cap., Pressure Advance "Down", Rapid "Up" Travel of Platen, Ejector "Up", Ejector "Retract" with motor drive oil hydraulic power system.

Overall Length Above Floor 23'9-1/2", Below Floor 6'6" x 18' L-R x 11' F-B

Total Weight 412,000 Lbs. Approx.

Press was operated from a central hydraulic pumping system. As such, no pumping system is included. We can supply a new one to customer's requirement at additional cost.

F.O.B. trucks, Lester, Pennsylvania



Visit our website at www.modernhydraulic.com